



## **Steps for Testing your Security System Should be done on a monthly basis**

- 1. Call the monitoring company to inform you are conducting a test**
- 2. Arm your system by putting in your user code**
- 3. Wait the exit delay period (usually 60 seconds)**
- 4. Open door or window to activate siren**
- 5. Allow siren to sound for at least 10 seconds to insure transmission of signal**
- 6. Disarm system by putting in your user code**
- 7. Call the monitoring company and let them know you are finished with test. If you are conducting test for transmission of signal ask representative if signal was received**

**If there is a question as to whether or not the system is working properly contact Marshall Alarm Systems at (914) 962-4699**